

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

Tender No: BBMP/EE/DD/Ten/09/2012-13, Date:16.03.2013

Item No: 23

SCHEDULE-B


NAME OF WORK: Construction of RCC drains at Bhuvaneshwari nagar 2nd cross road in Dasarahalli ward no.15.)

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor B UMESH	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	375.00	80.00	Rupees Eighty Only
2	Plain cement concrete 1:3:6 mix with crushed stone aggregates 40mm nominal size mechanically mixed, placed in foundation and compacted by vibration including curing for 14days complete as per specifications.	Cum	39.15	3400.00	Rupees Three Thousand Four Hundred Only
3	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted vibrating curing and necessary steel or ply wood or plank centering and form work etc., including smooth finish in CM 1:3,with all lead and lift etc., complete. (exclusive of cost of steel and fabrication charges) Ready mixed cement concrete for beams, columns, staircase and roof with M-20(Cement-320 kg/cum) complete as per specifications.	Cum	104.40	5200.00	Rupees Five Thousand Two Hundred Only
4	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	q	63.00	7000.00	Rupees Seven Thousand Only
5	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specifications.	Sqm	1160.00	285.00	Rupees Two Hundred Eighty Five Only
6	Supplying and fixing precast reinforced concrete slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials. complete as per specifications.	Sqm	261.00	1500.00	Rupees One Thousand Five Hundred Only


Signature of the Contractor

Executive Engineer

Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 K1 a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading. complete as per specifications.	Cum	375.00	74.00	Rupees Seventy Four Only
---	-----	--------	-------	--------------------------



Signature of the Contractor



Executive Engineer,
Dasarahalli Division,